

# 数 量 集 計 表

工事名:湖北南処理分区舗装復旧工事

工 種 ・ 細 目	規 格		設計数量	単位	備 考
道路修繕					
舗装工					
舗装打換え工					
舗装版切断	アスファルト t=15cm以下	6.05+3.95+170.0+3.95+5.00+5.00+5.35+3.20+11.45+10.95+2.95+2.9+2.9	233.70	230	m
舗装版破碎	アスファルト t=15cm以下	145.8+69.0+616.0	830.8	830	m2
運搬処理工					
殻運搬	アスファルト殻 22.0km以下	145.8*0.03+69.0*0.05+616.0*0.10	69.4	69	m3
殻処分	アスファルト殻		69.4	69	m3
道路土工					
路肩盛土工					
路肩盛土	山土 t=10cm	107*0.4*0.1	4.3	4.3	m3
舗装工					
舗装準備工					
不陸整正	補足材有 平均厚t=70mm M-30 67mm以上75mm未満	616.0+145.8=	761.8	762	m2
不陸整正	補足材有 平均厚t=30mm M-30 29mm以上34mm未満		69.0	69	m2
アスファルト舗装工					

# 数量集計表

工事名：湖北南处理分区舗装復旧工事

[illegible]

[illegible]

## 数 量 計 算 書

工事名: 湖北南処理分区舗装復旧工事

測 点	区間距離	表層(3.0m超)			表層(1.4m以上3.0m以下)								
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積						
1 + 93.3	4.70	6.10	5.80	27.3									
No.2	6.70	6.60	6.35	42.5									
2 + 15.0	15.0	6.20	6.40	96.0									
2 + 18.0	3.00	11.00	8.60	25.8									
2 + 23.0	5.0	10.40	10.70	53.5									
2 + 23.0		9.00											
2 + 23.9	0.90	5.10	7.05	6.3									
No.0'		5.10											
+ 8.0	8.0	5.35	5.23	41.8									
No.0		3.20											
+ 4.65	4.65	3.20	3.20	14.9									
+ 4.65		4.35											
+ 15.60	10.95	3.85	4.10	44.9									
+ 17.00	1.40	2.95	3.40	4.8									
1.5×2.9				4.4									
計	248.9			473.2			357.0						

## 数 量 計 算 書

工事名: 湖北南処理分区舗装復旧工事

測 点	区間距離	舗装版破碎(t=3cm) 不陸整正(平均厚t=70mm)			舗装版破碎(t=5cm) 不陸整正(平均厚t=30mm)			舗装版破碎(t=10cm) 不陸整正(平均厚t=70mm)					
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	断面	平 均 断 面	平 積			
											不陸整正(平均厚72mm) $A=145.8+616.0=761.8m^2$ $761.8 \times 0.07=53.326m^3$ $293 \times 0.65 \times 0.03=5.714m^3$ $60.944-5.714=55.230m^3$ $55.230 \div 761.8=0.062$ 平均厚=70mm		
No.0		0.65						5.40					
0 + 10.0	10.0	0.65	0.65	6.5				5.40	5.40	54.0			
0 + 10.0		0.65						1.45					
0 + 20.0	10.0	0.65	0.65	6.5				1.45	1.45	14.5			
0 + 40.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
0 + 60.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
0 + 80.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
No.1	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
1 + 20.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
1 + 40.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
1 + 60.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
1 + 80.0	20.0	0.65	0.65	13.0				1.45	1.45	29.0			
1 + 80.0		0.65						5.40					
1 + 87.0	7.00	0.65	0.65	4.6				5.35	5.38	37.7			
1 + 87.0		0.65						4.55					
1 + 88.6	1.60	0.65	0.65	1.0				4.55	4.55	7.3			
1 + 88.6		0.65						4.85					

## 数 量 計 算 書

工事名:湖北南処理分区分舗装復旧工事

測 点	区間距離	舗装版破碎(t=3cm) 不陸整正(平均厚t=70mm)			舗装版破碎(t=5cm) 不陸整正(平均厚t=30mm)			舗装版破碎(t=10cm) 不陸整正(平均厚t=70mm)					
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	断面	平 均 断 面	平 積			
1 + 93.3	4.70	0.65	0.65	3.1				5.45	5.15	24.2			
No.2	6.70	0.65	0.65	4.4				5.95	5.70	38.2			
2 + 15.0	15.0	0.65	0.65	9.8				5.55	5.75	86.3			
2 + 18.0	3.00	0.65	0.65	2.0				10.35	7.95	23.9			
2 + 23.0	5.00	0.65	0.65	3.3				9.75	10.05	50.3			
2 + 23.0		0.65						8.35					
2 + 23.9	0.90	0.65	0.65	0.6				4.45	6.40	5.8			
No.0								5.10					
+ 8.0	8.00							5.35	5.23	41.8			
No.0					3.20								
+ 4.65	4.65				3.20	3.20	14.9						
+ 4.65					4.35								
+ 15.60	10.95				3.85	4.10	44.9						
+ 17.00	1.40				2.95	3.40	4.8						
1.5×2.9							4.4						
計	248.9			145.8			69.0			616.0			