

# 本 工 事 数 量 集 計 表

No. 1

工 種 ・ 細 目	規 格	算 式	設計数量	単位	備 考
道路修繕		1.0	1	式	
舗装工		1.0	1	式	
舗装打換え工		1.0	1	式	
舗装版切断	アスファルト舗装版 t=15cm以下	3.2+7.3+1.0+4.4	15.9	16	m
舗装版破碎	アスファルト舗装版 t=15cm以下	265.2+366.9-2.75*0.35	631.1	631	m2
殻運搬	アスファルト殻	(265.2+366.9-2.75*0.35)*0.05	31.6	32	m3
殻処分	アスファルト殻	(265.2+366.9-2.75*0.35)*0.05	31.6	32	m3
不陸整正	補足材有、粒度調整碎石(M-30) t=平均3cm	203.2+243.3-2.75*0.35	445.5	446	m2
不陸整正	補足材有、粒度調整碎石(M-30) t=平均3cm	62.0+123.6	185.6	186	m2
表層	再生密粒度As(20) W=1.4m以上3.0m以下 t=5cm	203.2+243.3-2.75*0.35	445.5	446	m2
表層	再生密粒度As(20) W=3.0m超 t=5cm	62.0+123.6	185.6	186	m2
仮設工		1.0	1	式	
交通管理工		1.0	1	式	
交通誘導警備員	交通誘導警備員B	1.0	1.0	1	式

数 量 計 算 書

L側 No. 1

測 点	区間距離	舗装版破碎			不陸整正			表層			断面	平均 断面	立 積
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積			
No.0 +		3.20			3.20			3.20					
No.0 + 20.0	20.0	3.00	3.10	62.0	3.00	3.10	62.0	3.00	3.10	62.0			
小 計	20.0			62.0			62.0			62.0			
No.0 + 20.0		3.00			3.00			3.00					
No.0 + 40.0	20.0	2.85	2.93	58.6	2.85	2.93	58.6	2.85	2.93	58.6			
No.0 + 60.0	20.0	2.70	2.78	55.6	2.70	2.78	55.6	2.70	2.78	55.6			
No.0 + 80.0	20.0	2.90	2.80	56.0	2.90	2.80	56.0	2.90	2.80	56.0			
No.0 + 89.85	9.9	3.00	2.95	29.2	3.00	2.95	29.2	3.00	2.95	29.2			
No.0 + 91.7	1.9	1.00	2.00	3.8	1.00	2.00	3.8	1.00	2.00	3.8			
小 計	71.8			203.2			203.2			203.2			
合 計	91.8			265.2			265.2			265.2			

数 量 計 算 書

R側 No. 2

測 点	区間距離	舗装版破碎			不陸整正			表層			断面	平均断面	立 積
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積			
No.0 + 0.35		2.50			2.50			2.50					
No.0 + 20.0	19.7	2.60	2.55	50.2	2.60	2.55	50.2	2.60	2.55	50.2			
No.0 + 40.0	20.0	2.60	2.60	52.0	2.60	2.60	52.0	2.60	2.60	52.0			
No.0 + 60.0	20.0	2.70	2.65	53.0	2.70	2.65	53.0	2.70	2.65	53.0			
No.0 + 80.0	20.0	2.80	2.75	55.0	2.80	2.75	55.0	2.80	2.75	55.0			
No.0 + 90.0	10.0	2.50	2.65	26.5	2.50	2.65	26.5	2.50	2.65	26.5			
No.0 + 91.9	1.9	4.40	3.45	6.6	4.40	3.45	6.6	4.40	3.45	6.6			
小 計	91.6			243.3			243.3			243.3			
No.0 + 91.9		4.40			4.40			4.40					
No.1 +	8.1	4.40	4.40	35.6	4.40	4.40	35.6	4.40	4.40	35.6			
No.1 + 20.0	20.0	4.40	4.40	88.0	4.40	4.40	88.0	4.40	4.40	88.0			
小 計	28.1			123.6			123.6			123.6			
合 計	119.7			366.9			366.9			366.9			