

数 量 集 計 表

春近地区

No. 1

工 種 ・ 細 目	規 格	算 式		単位	備 考
<土工>					
床掘	人力 BH0.28m3	12.8	12.8	13	m3
埋戻1	小規模	24.0	24.0	24	m3
埋戻2	小規模	8.0	8.0	8	m3
埋戻材	山土	24.0+8.0-12.8=19.2	19.2	19	m3
土砂等運搬	4t L=0.2km以下	12.8	12.8	13	m3
法面整形		52.8	52.8	53	m2
<構造物工>					
底打ちコンクリート	18-8-40BB	194.4*0.1=19.4	19.4	19	m3
<仮設工>					
大型土のう工	製作・設置 流用土	3.0	3	3	袋
大型土のう工	撤去	3.0	3	3	袋
排水ポンプ据付撤去	小口径 100mm	1.0	1	1	箇所
排水ポンプ運転	小口径 100mm 常時排水	1.0	1	1	箇所 運転日数 16日
敷鉄板設置撤去工	設置・撤去	3.048*1.524*102=473.8 (102*0.802=81.8t)	473.8	474	m2
敷鉄板賃料	22*3048*1524 802kg/枚	102.0	102.0	102	枚 供用日数 24日
<交通管理工>					
交通管理工	交通誘導警備員B	1.0	1.0	1	式 14人

数 量 計 算 書

No.1

測 点	区間距離	床掘			埋戻1			埋戻2					
		面 積	平 均 面 積	立 積	面 積	平 均 面 積	立 積	面 積	平 均 面 積	立 積			
0 + 0.00	0.00	0.0			0.3			0.2					
+ 40.00	40.00	0.0	0.00	0.0	0.3	0.30	12.0	0.1	0.15	6.0			
+ 80.00	40.00	0.1	0.05	2.0	0.3	0.30	12.0	0.0	0.05	2.0			
+ 80.00	0.00	0.1			0.0			0.0					
1 + 20.00	40.00	0.2	0.15	6.0	0.0	0.00	0.0	0.0	0.00	0.0			
1 + 44.00	24.00	0.2	0.20	4.8	0.0	0.00	0.0	0.0	0.00	0.0			
合計	144.00			12.8			24.0			8.0			

数 量 計 算 書

No.2

測 点	区間距離	底打ちコンクリート			法面整形								
		延 長	平 均 延 長	面 積	延 長	平 均 延 長	面 積						
0 + 0.00	0.00	1.51			0.66								
+ 40.00	40.00	1.51	1.51	60.4	0.66	0.66	26.4						
+ 80.00	40.00	1.51	1.51	60.4	0.66	0.66	26.4						
+ 80.00	0.00	1.51			0.00		0.0						
1 + 20.00	40.00	1.51	1.51	60.4	0.00	0.00	0.0						
1 + 44.00	24.00	1.51	1.51	36.2	0.00	0.00	0.0						
		アーム部材控除 (144/1.5-1)											
		1.51*0.16*95		(23.0)									
合計	144.00			194.4			52.8						