

No. 1

[illegible]

本 工 事 数 量 集 計 表

No. 2

工種・細目	規格	算 式	設計数量	単位	備考
<土工>					
床掘り	小規模	$\begin{array}{ccccccc} \text{横断部} & \text{控除} & \text{土のう起点側} & \text{土のう終点側} \\ 84.90 + & 2.50 - & 1.50 + & 0.10 * & 1.00 + & 0.10 * & 1.00 = 86.10 \end{array}$	86	m3	
埋戻し	小規模	$\begin{array}{ccccccc} \text{横断部} & \text{控除} & & & & & \\ 50.20 + & 1.10 - & 0.5 = & 50.80 & & & \end{array}$	51	m3	
運搬	土砂 現場～仮置場～現場	50.80	51	m3	
運搬	土砂 現場～処分場	$86.10 * 0.90 - 50.8 = 26.7$	27	m3	
残土処分	土砂	26.70	27	m3	
<構造物工>					
重力式擁壁工	H1800	1.0	1	式	
横断水路工	300*300	5.0	5	m	
取付水路工	300*300	0.7	1	m	
植生土のう工		$0.4 + 0.4 = 0.8$	1	m2	
<舗装復旧工>					
路盤	1層施工 100mm 粒度調整碎石 (M-30)	$42.70 - 0.52 * 1.56 + (0.30 + 0.30) * 3.44 = 44.00$	44.0	m2	
不陸整正	補足材有 補足材 (M-30) 平均t=3cm	$28.10 - 1.22 * 0.94 + (0.20 + 0.20) * 2.50 = 28.00$	28.0	m2	
表層	車道・路肩部 1.4m以上 再生密粒度AS(13) t=5cm	$70.60 - 0.52 * 2.50 + (0.50 + 0.50) * 2.50 = 71.80$	71.8	m2	

数 量 計 算 書

No. 1

測 点	区間距離	床堀			埋戻し								
		断 面	平 均 断面	立 積	断 面	平 均 断面	立 積	断 面	平 均 断面	立 積	断 面	平 均 断面	立 積
No.0 + 0.00		0.00			0.00								
No.0 + 0.54	0.54	3.40	1.70	0.9	1.80	0.90	0.5						
No.0 + 5.00	4.46	2.80	3.10	13.8	1.80	1.80	8.0						
No.0 + 10.00	5.00	3.10	2.95	14.8	1.90	1.85	9.3						
No.1	10.00	3.10	3.10	31.0	1.80	1.85	18.5						
No.1 + 5.00	5.00	3.10	3.10	15.5	1.80	1.80	9.0						
No.1 7.46	2.46	3.40	3.25	8.0	1.80	1.80	4.4						
No.1 + 8.00	0.54	0.00	1.70	0.9	0.00	0.90	0.5						
合 計	28.0			84.9			50.2						

数 量 計 算 書

No. 2

測 点	区間距離	舗装版破碎			上層路盤(10cm)			不陸整正(3cm)			表層		
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積
No.0 + 0.00		2.65			0.50			2.15			2.65		
No.0 + 0.54	0.54	2.65	2.65	1.4	1.56	1.03	0.6	1.09	1.62	0.9	2.65	2.65	1.4
No.0 + 5.00	4.46	2.50	2.58	11.5	1.54	1.55	6.9	0.96	1.03	4.6	2.50	2.58	11.5
No.0 + 10.00	5.00	2.50	2.50	12.5	1.54	1.54	7.7	0.96	0.96	4.8	2.50	2.50	12.5
No.1	10.00	2.50	2.50	25.0	1.54	1.54	15.4	0.96	0.96	9.6	2.50	2.50	25.0
No.1 + 5.00	5.00	2.50	2.50	12.5	1.54	1.54	7.7	0.96	0.96	4.8	2.50	2.50	12.5
No.1 7.46	2.46	2.65	2.58	6.3	1.58	1.56	3.8	1.07	1.02	2.5	2.65	2.58	6.3
No.1 + 8.00	0.54	2.65	2.65	1.4	0.50	1.04	0.6	2.15	1.61	0.9	2.65	2.65	1.4
合 計	28.0			70.6			42.7			28.1			70.6

[illegible]

[illegible]