

本 工 事 数 量 集 計 表

No. 1

工種・細目	規格	算 式	設計数量	単位	備考
<取壊工>					
舗装版切断	アスファルト舗装版 t=15cm以下	$4.0 + 4.1 = 8.1$	8.1	8	m
舗装版破碎積込	小規模	28.30	28.3	28	m ²
殻運搬	舗装破碎、機械積込 小規模 28.5km以下	$28.3 * 0.05 = 1.4$	1.4	1	m ³
処分費	アスファルト塊	1.4	1.4	1	m ³
構造物とりこわし	鉄筋構造物 人力施工	$0.331 / 2.00 * 4.00 / 2.50 = 0.3$	0.3	0.3	m ³
ダンプトラック運搬	コンクリート塊 2t 人力 17.4km	0.3	0.3	0.3	m ³
処分費	鉄筋コンクリート塊	0.3	0.3	0.3	m ³
<土工>					
床掘り	小規模	$64.50 + \text{横断部} 1.3 + \text{呑口部} 0.3 - \text{横断控除} 0.8 = 65.30$	65.3	65	m ³
埋戻し	小規模	$37.80 + \text{横断部} 0.50 - \text{横断控除} 0.7 = 37.60$	37.6	38	m ³
運搬	土砂 現場～仮置場～現場	37.60	37.6	38	m ³
運搬	土砂 現場～処分場	$65.30 * 0.90 - 37.6 = 21.2$	21.2	21	m ³
残土処分	土砂	21.20	21.2	21	m ³

No. 2

[illegible]

測 点	区間距離	床堀			埋戻し								
		断 面	平 均 断 面	立 積	断 面	平 均 断 面	立 積	断 面	平 均 断 面	立 積	断 面	平 均 断 面	立 積
No.0 + 0.00		0.00			0.00								
No.0 + 1.15	1.15	11.20	5.60	6.4	6.40	3.20	3.7						
No.0 + 3.00	1.85	11.20	11.20	20.7	6.40	6.40	11.8						
No.0 + 5.00	2.00	11.00	11.10	22.2	6.70	6.55	13.1						
No.0 + 5.75	0.75	11.00	11.00	8.3	6.70	6.70	5.0						
No.0 7.00	1.25	0.00	5.50	6.9	0.00	3.35	4.2						
合 計	7.0			64.5			37.8						

数 量 計 算 書

No. 2

測 点	区間距離	舗装版破碎			上層路盤(10cm)			不陸整正(3cm)			表層		
		幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積	幅 員	平 均 幅 員	平 積
No.0 + 0.00		4.00			0.50			3.10			3.60		
No.0 + 1.15	1.15	4.00	4.00	4.6	2.45	1.48	1.7	1.30	2.20	2.5	3.75	3.68	4.2
No.0 + 3.00	1.85	4.00	4.00	7.4	2.50	2.48	4.6	1.50	1.40	2.6	4.00	3.88	7.2
No.0 + 5.00	2.00	4.10	4.05	8.1	2.55	2.53	5.1	1.55	1.53	3.1	4.10	4.05	8.1
No.0 + 5.75	0.75	4.10	4.10	3.1	2.55	2.55	1.9	1.55	1.55	1.2	4.10	4.10	3.1
No.0 7.00	1.25	4.10	4.10	5.1	0.50	1.53	1.9	3.60	2.58	3.2	4.10	4.10	5.1
合 計	7.0			28.3			15.2			12.6			27.7

H3.844~4.205

1式当り

[illegible]