

本 工 事 数 量 集 計 表

市道八幡中山大井川添線舗装修繕工事

工 種 ・ 細 目	規 格	算 式	設計数量	単位	備 考
道路修繕		1.0	1	式	
舗装工		1.0	1	式	
舗装打換え工		1.0	1	式	
舗装版切断	舗装版種別アスファルト舗装版； 舗装厚50mm	$5.6+5.0+1.8+1.95+0.4+6.2+1.5=22.5$ 22.5	23	m	
舗装版破碎(小規模)	舗装版種別アスファルト舗装版	数量計算書より $263.2+20.5+118.4+170.0+49.0=621.1$ 621.1	621	m2	
舗装版破碎	舗装版種別アスファルト舗装版； 舗装版厚5cm	数量計算書より $26.1+52.1+3.0=81.2$ 81.2	81	m2	
殻運搬	殻種別舗装版破碎	$(621.1+81.2)*0.05=35.1$ 35.1	35	m3	
殻処分	殻種別アスファルト殻	$(621.1+81.2)*0.05=35.1$ 35.1	35	m3	
不陸整正	補足材有、粒度調整碎石M-30； 仕上り厚平均30mm	数量計算書より $309.8+118.4+274.1=702.3$ 702.3	702	m2	
表層	材料種類再生密粒度アスコン(13)；舗装厚50mm； 平均幅員1.4m未満(1層当り平均仕上り厚50mm以下)	数量計算書より $32.4+53.7+118.4+56.7+3.0=264.2$ 264.2	264	m2	
表層	材料種類再生密粒度アスコン(13)；舗装厚50mm； 平均幅員1.4m以上3.0m以下	数量計算書より $134.9+88.8+165.4+49.0=438.1$ 438.1	438	m2	
付帯工		1.0	1	式	
人孔蓋調整		1.0	1	組	
区画線工		1.0	1	式	
区画線工		1.0	1	式	
熔融式区画線	施工方法区分熔融式手動；規格・仕様区分 実線15cm；塗布厚厚1.5mm；排水性舗装無し	$49.9+0.45+0.75+5.2=56.3$ 56.3	56	m	
熔融式区画線	施工方法区分熔融式手動；規格・仕様区分 破線15cm；塗布厚厚1.5mm；排水性舗装無し	15.0	15	m	

本 工 事 数 量 集 計 表

市道八幡中山大井川添線舗装修繕工事

[illegible]

数 量 計 算 書

No.1

市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	舗装版破碎(小規模)								
			平 均 幅 員	平 積						
西側右① No.0		5.60								
No.0		3.90	4.75	57.0						
No.0	+ 12.0	12.0	3.25	3.58	21.1					
No.0	+ 17.9	5.9	2.15							
No.0	+ 17.9'	0.0	1.50	1.83	3.8					
No.0	+ 20.0	2.1	1.40	1.45	1.5					
No.0	+ 21.0	1.0	1.65	1.53	29.1					
No.0	+ 40.0	19.0	1.70	1.68	6.7					
No.0	+ 44.0	4.0	1.15	1.43	15.7					
No.0	+ 55.0	11.0	1.20	1.18	5.9					
No.0	+ 60.0	5.0	1.50	1.35	10.4					
No.0	+ 67.7	7.7	1.20	1.35	9.3					
No.0	+ 74.6	6.9	1.30	1.25	6.8					
No.0	+ 80.0	5.4	1.50	1.40	10.8					
No.0	+ 87.7	7.7	1.60	1.55	9.9					
No.0	+ 94.1	6.4	1.65							
No.0	+ 94.1'	0.0	1.70	1.68	9.9					
No.1		5.9	1.65	1.68	6.9					
No.1	+ 4.1	4.1	1.60							
No.1	+ 4.1'	0.0	1.70	1.65	26.2					
No.1	+ 20.0	15.9	1.75	1.73	5.0					
No.1	+ 22.9	2.9	1.80	1.78	20.1					
No.1	+ 34.2	11.3	0.65	1.23	7.1					
No.1	+ 40.0	5.8								
小 計	140.0			263.2						
西側右② No.2'		0.50								
No.2		0.90	0.70	14.0						
No.2	+ 20.0	20.0	0.90	0.90	5.8					
No.2	+ 26.4	6.4	1.80	1.35	0.7					
No.2	+ 26.9	0.5								
小 計	26.9			20.5						

数 量 計 算 書

No.2
市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	舗装版破碎(小規模)								
			平 均 幅	平 積						
西側左		0.05								
No.1 + 22.9		1.60	0.83	14.2						
No.1 + 40.0	17.1	1.05	1.33	5.3						
No.1 + 44.0	4.0	1.15	1.10	17.6						
No.1 + 60.0	16.0	1.25	1.20	24.0						
No.1 + 80.0	20.0	1.20	1.23	9.6						
No.1 + 87.8	7.8	1.15	1.18	14.4						
No.2	12.2	1.15	1.15	23.0						
No.2 + 20.0	20.0	1.25	1.20	7.0						
No.2 + 25.8	5.8	1.90	1.58	1.6						
No.2 + 26.8	1.0	1.95	1.93	1.7						
No.2 + 27.7	0.9									
小 計	104.8			118.4						
東側右①		0.40								
No.1 + 20.0		1.25	0.83	4.6						
No.1 + 25.6	5.6	1.80	1.53	7.8						
No.1 + 30.7	5.1	2.35	2.08	19.3						
No.1 + 40.0	9.3	3.15	2.75	55.0						
No.1 + 60.0	20.0	3.00	3.08	23.1						
No.1 + 67.5	7.5	2.70	2.85	13.7						
No.1 + 72.3	4.8	2.10	2.40	18.5						
No.1 + 80.0	7.7	0.70	1.40	28.0						
No.2	20.0									
小 計	80.0			170.0						
東側右②		1.40								
No.2 + 5.6'		1.75	1.58	9.8						
No.2 + 11.8	6.2	1.60								
No.2 + 11.8'	0.0	2.05	1.83	4.0						
No.2 + 14.0	2.2	1.85	1.95	11.7						
No.2 + 20.0	6.0	1.50	1.68	23.5						
No.2 + 34.0	14.0									
小 計	28.4			49.0						
合 計	380.1			621.1						

測 点	区間距離	舗装版破砕(障害有)								
		幅 員	平 均 幅 員	平 積						
西側右		0.65								
No.1 + 40.0										
No.1 + 60.0	20.0	0.40	0.53	10.6						
No.1 + 80.0	20.0	0.30	0.35	7.0						
No.1 + 87.8	7.8	0.35	0.33	2.6						
No.2	12.2	0.60	0.48	5.9						
小 計	60.0			26.1						
東側右①		0.40								
No.0										
No.0 + 20.0	20.0	0.40	0.40	8.0						
No.0 + 40.0	20.0	0.45	0.43	8.6						
No.0 + 60.0	20.0	0.50	0.48	9.6						
No.0 + 80.0	20.0	0.45	0.48	9.6						
No.1	20.0	0.40	0.43	8.6						
No.1 + 14.7	14.7	0.35	0.38	5.6						
No.1 + 14.7'	0.0	0.45								
No.1 + 19.0	4.3	0.35	0.40	1.7						
No.1 + 20.0	1.0	0.40	0.38	0.4						
小 計	120.0			52.1						
東側右②		0.70								
No.2										
No.2 + 5.6	5.6	0.35	0.53	3.0						
小 計	5.6			3.0						
合 計	185.6			81.2						

西側右

市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	不陸整正								
		幅 員	平 均 幅 員	平 積						
No.0		5.60								
No.0	12.0	3.90	4.75	57.0						
No.0	17.9	3.25	3.58	21.1						
No.0	17.9'	2.15								
No.0	20.0	1.50	1.83	3.8						
No.0	21.0	1.40	1.45	1.5						
No.0	40.0	1.65	1.53	29.1						
No.0	44.0	1.70	1.68	6.7						
No.0	55.0	1.15	1.43	15.7						
No.0	60.0	1.20	1.18	5.9						
No.0	67.7	1.50	1.35	10.4						
No.0	74.6	1.20	1.35	9.3						
No.0	80.0	1.30	1.25	6.8						
No.0	87.7	1.50	1.40	10.8						
No.0	94.1	1.60	1.55	9.9						
No.0	94.1'	1.65								
No.1	5.9	1.70	1.68	9.9						
No.1	4.1	1.65	1.68	6.9						
No.1	4.1'	1.60								
No.1	20.0	1.70	1.65	26.2						
No.1	22.9	1.75	1.73	5.0						
No.1	34.2	1.80	1.78	20.1						
No.1	40.0	0.65	1.23	7.1						
No.1	60.0	0.40	0.53	10.6						
No.1	80.0	0.30	0.35	7.0						
No.1	87.8	0.35	0.33	2.6						
No.2	12.2	0.60	0.48	5.9						
No.2'	0.0	0.50								
No.2	20.0	0.90	0.70	14.0						
No.2	26.4	0.90	0.90	5.8						
No.2	26.9	1.80	1.35	0.7						
小 計	226.9			309.8						

西側左

市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	不陸整正								
		幅 員	平 均 幅 員	平 積						
No.1 + 22.9		0.05								
No.1 + 40.0	17.1	1.60	0.83	14.2						
No.1 + 44.0	4.0	1.05	1.33	5.3						
No.1 + 60.0	16.0	1.15	1.10	17.6						
No.1 + 80.0	20.0	1.25	1.20	24.0						
No.1 + 87.8	7.8	1.20	1.23	9.6						
No.2	12.2	1.15	1.18	14.4						
No.2 + 20.0	20.0	1.15	1.15	23.0						
No.2 + 25.8	5.8	1.25	1.20	7.0						
No.2 + 26.8	1.0	1.90	1.58	1.6						
No.2 + 27.7	0.9	1.95	1.93	1.7						
小 計	104.8			118.4						

東側右

市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	不陸整正								
		幅 員	平 均 幅 員	平 積						
No.0		0.40								
No.0 + 20.0	20.0	0.40	0.40	8.0						
No.0 + 40.0	20.0	0.45	0.43	8.6						
No.0 + 60.0	20.0	0.50	0.48	9.6						
No.0 + 80.0	20.0	0.45	0.48	9.6						
No.1	20.0	0.40	0.43	8.6						
No.1 + 14.7	14.7	0.35	0.38	5.6						
No.1 + 14.7'	0.0	0.45								
No.1 + 19.0	4.3	0.35	0.40	1.7						
No.1 + 20.0	1.0	0.40	0.38	0.4						
No.1 + 25.6	5.6	1.25	0.83	4.6						
No.1 + 30.7	5.1	1.80	1.53	7.8						
No.1 + 40.0	9.3	2.35	2.08	19.3						
No.1 + 60.0	20.0	3.15	2.75	55.0						
No.1 + 67.5	7.5	3.00	3.08	23.1						
No.1 + 72.3	4.8	2.70	2.85	13.7						
No.1 + 80.0	7.7	2.10	2.40	18.5						
No.2	20.0	0.70	1.40	28.0						
No.2 + 5.6	5.6	0.35	0.53	3.0						
No.2 + 5.6'	0.0	1.40								
No.2 + 11.8	6.2	1.75	1.58	9.8						
No.2 + 11.8'	0.0	1.60								
No.2 + 14.0	2.2	2.05	1.83	4.0						
No.2 + 20.0	6.0	1.85	1.95	11.7						
No.2 + 34.0	14.0	1.50	1.68	23.5						
小 計	234.0			274.1						
合 計	565.7			702.3						

数 量 計 算 書

No.7
市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	表層(平均幅員1.4m未満)								
		幅 員	平 均 幅 員	平 積						
西側右①		1.15								
No.0 + 55.0		1.20	1.18	5.9						
No.0 + 60.0	5.0	1.50	1.35	10.4						
No.0 + 67.7	7.7	1.20	1.35	9.3						
No.0 + 74.6	6.9	1.30	1.25	6.8						
No.0 + 80.0	5.4									
小 計	25.0			32.4						
西側右②		1.80								
No.1 + 34.2		0.65	1.23	7.1						
No.1 + 40.0	5.8	0.40	0.53	10.6						
No.1 + 60.0	20.0	0.30	0.35	7.0						
No.1 + 80.0	20.0	0.35	0.33	2.6						
No.1 + 87.8	7.8	0.60	0.48	5.9						
No.2	12.2	0.50								
No.2'	0.0	0.90	0.70	14.0						
No.2 + 20.0	20.0	0.90	0.90	5.8						
No.2 + 26.4	6.4	1.80	1.35	0.7						
No.2 + 26.9	0.5									
小 計	92.7			53.7						
西側左		0.05								
No.1 + 22.9		1.60	0.83	14.2						
No.1 + 40.0	17.1	1.05	1.33	5.3						
No.1 + 44.0	4.0	1.15	1.10	17.6						
No.1 + 60.0	16.0	1.25	1.20	24.0						
No.1 + 80.0	20.0	1.20	1.23	9.6						
No.1 + 87.8	7.8	1.15	1.18	14.4						
No.2	12.2	1.15	1.15	23.0						
No.2 + 20.0	20.0	1.25	1.20	7.0						
No.2 + 25.8	5.8	1.90	1.58	1.6						
No.2 + 26.8	1.0	1.95	1.93	1.7						
No.2 + 27.7	0.9									
小 計	104.8			118.4						

数 量 計 算 書

No.8

市道八幡中山大井川添線舗装修繕工事

測 点	区間距離	表層(平均幅員1.4m未満)								
		幅 員	平 均 幅 員	平 積						
東側右① No.0		0.40								
No.0 + 20.0	20.0	0.40	0.40	8.0						
No.0 + 40.0	20.0	0.45	0.43	8.6						
No.0 + 60.0	20.0	0.50	0.48	9.6						
No.0 + 80.0	20.0	0.45	0.48	9.6						
No.1	20.0	0.40	0.43	8.6						
No.1 + 14.7	14.7	0.35	0.38	5.6						
No.1 + 14.7'	0.0	0.45								
No.1 + 19.0	4.3	0.35	0.40	1.7						
No.1 + 20.0	1.0	0.40	0.38	0.4						
No.1 + 25.6	5.6	1.25	0.83	4.6						
小 計	125.6			56.7						
東側右② No.2		0.70								
No.2 + 5.6	5.6	0.35	0.53	3.0						
小 計	5.6			3.0						
合 計	353.7			264.2						

測 点	区間距離	表層(平均幅員1.4m以上3.0m以下)								
		幅 員	平 均 幅 員	平 積						
西側右① No.0		5.60								
No.0 + 12.0	12.0	3.90	4.75	57.0						
No.0 + 17.9	5.9	3.25	3.58	21.1						
No.0 + 17.9'	0.0	2.15								
No.0 + 20.0	2.1	1.50	1.83	3.8						
No.0 + 21.0	1.0	1.40	1.45	1.5						
No.0 + 40.0	19.0	1.65	1.53	29.1						
No.0 + 44.0	4.0	1.70	1.68	6.7						
No.0 + 55.0	11.0	1.15	1.43	15.7						
小 計	55.0			134.9						
西側右② No.0 + 80.0		1.30								
No.0 + 87.7	7.7	1.50	1.40	10.8						
No.0 + 94.1	6.4	1.60	1.55	9.9						
No.0 + 94.1'	0.0	1.65								
No.1	5.9	1.70	1.68	9.9						
No.1 + 4.1	4.1	1.65	1.68	6.9						
No.1 + 4.1'	0.0	1.60								
No.1 + 20.0	15.9	1.70	1.65	26.2						
No.1 + 22.9	2.9	1.75	1.73	5.0						
No.1 + 34.2	11.3	1.80	1.78	20.1						
小 計	54.2			88.8						
東側右① No.1 + 25.6		1.25								
No.1 + 30.7	5.1	1.80	1.53	7.8						
No.1 + 40.0	9.3	2.35	2.08	19.3						
No.1 + 60.0	20.0	3.15	2.75	55.0						
No.1 + 67.5	7.5	3.00	3.08	23.1						
No.1 + 72.3	4.8	2.70	2.85	13.7						
No.1 + 80.0	7.7	2.10	2.40	18.5						
No.2	20.0	0.70	1.40	28.0						
小 計	74.4			165.4						
東側右② No.2 + 5.6'		1.40								
No.2 + 11.8	6.2	1.75	1.58	9.8						
No.2 + 11.8'	0.0	1.60								
No.2 + 14.0	2.2	2.05	1.83	4.0						
No.2 + 20.0	6.0	1.85	1.95	11.7						
No.2 + 34.0	14.0	1.50	1.68	23.5						
小 計	28.4			49.0						
合 計	212.0			438.1						